



B-1 LEVEL QUANTITY SCHEDULE	
SURFACE AREA	1,500 SQUARE FEET

LEGEND	
	DUST CONTROL

- NOTES
1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION OF HEPA VACUUMING AND WET METHOD CLEANING IN THIS AREA INCLUDING TRAILING CONDUITS.
 2. AREA SHALL BE ISOLATED WITH POLYETHYLENE SHEETING, IN VACUUM FOR CLEANING. A LEAK TEST SHALL BE USED FOR NEGATIVE AIR PRESSURE. PERSONAL PROTECTIVE RESPIRATORY PROTECTION, A UNIT SHALL BE USED.